



Advancement of HL-LHC CCT Prototype and Schedule of Series in China

Qingjin XU

IHEP-CAS, Beijing, China





21 January 2020 - HKUST




Table of contents

- Reminder of Collaboration scope and deliverables
- Status of work
- Steering Committee meetings: Main outcome
- Present schedule
- Manpower and structure
- Risks, impact, mitigation measures
- Summary

MCBRD: the HL-LHC D2 orbit correctors, providing a **maximum 5 Tm integrated field** in two apertures, **vertical in one and horizontal in the other**.



Agreement For HL-LHC CCT magnets signed in September 2018





DOE
Nb3Sn
R&D



FP6
CARE
Nb3Sn

CERN-
KEK R&D

LARP
HiField
quads

FP7
EuCARD
HiField
Dip

FP7
sLHC PP
(INJ)

KEK D1
design and
constru
ction

LARP
Demo

FP7 DS
Hi-Lumi LHC

sLHC INJ
implem.



BINP+...
Absorbers
CC ampli.
e-lens?...

TRIUMF
CC
cryostat

IHEP
CCT
corrector


Project DS started

today

HL-LHC
Construction

Injector
upgrade

HL-LHC
install.& comm.



Non binding MoU
for HL-LHC

The time for
"booking" in-kind
contributions is
shrinking!
Certain items
require a long
qualification
process for
companies and
also for Labs



Reminder of collaboration scope and deliverables

IHEP's contribution in general


- A **Quality Assurance (QA) and a Quality Control (QC) plan** in accordance with CERN and HL-LHC guidelines,
- A **full-size prototype** of the MCBRD orbit corrector magnet;
- A series of **twelve MCBRD orbit corrector magnets (8 plus 4 spares)**;
- The room temperature **magnetic measurements** of all the magnets to validate the quality of the assembly;
- The **vertical test at 4.2 K** of the prototype and of the series magnets;
- The **documentation relative to the production** of the MCBRD corrector magnets in due time for review and acceptance by CERN;
- The **documentation relative to the results of performance** evaluation tests of each MCBRD orbit corrector in due time for review and acceptance by CERN; and
- All **tooling** agreed between the Parties as necessary for the maintenance and repair at CERN of each series production MCBRD orbit corrector magnet over the HL-LHC operational life

Status of work - Superconducting Wires

- NbTi bare wire for the 1st 2.2m prototype from WST China.
- The insulation done by CGP France. No J_c decay after insulation.

“After correcting for the higher Cu:non-Cu ratio the WST strand is about 7% more performance than the MB outer layer strand.”-Matthias

WST strand versus MB outer layer strand fitting, corrected for Cu:non-Cu ratio of 1.3




Status of work - Coil Formers

- Formers for the 2.2m Prototype (HE-Racing China)
 - Inner former, outer former and former assemblies for the two apertures completed and delivered to WST.
 - The anodized thickness of formers is 40-50 μm .




Former assemblies



Dimension measurement





Anodized former and external support tube




Q. Xu, IAS Program on HEP, HKUST, 21 Jan 2020

Status of work - CCT Coils




Advancement of VPI for Aperture V

- Coil VPI for aperture V and H completed
 - ✓ Baking coil before vacuum impregnation at 80°C for 3 days.
 - ✓ Electrical test before and after VPI procedure




Aperture V coil after VPI

VPI for Aperture V



Status of work - Yoke

- Yoke Steel Delivery
 - 1st : About 10 tons yoke steel for the 1st 2.2m prototype have been received in February 2019.
 - 2nd : 40 tons yoke steel has been received in December 2019.
- Yoke laminations (KEYE, Anhui, China)
 - End plates machining and dimension measurement → completed
 - Yoke lamination machining and dimension measurement → completed





Status of work - Preparation of Test station

LHe recovery


- Gas bag → 200 m³
- Recovery compressor → 80 m³/h
- Impure Gas Storage → > 10 m³ @ 15MPa
- External Purifier → 75 m³/h
- Vertical Dewar → Φ 800 x 3800 mm

Test Dewar



- + Valve box for Vertical Test Dewar
- + Pre-cooler system for cooling down warm up



Scheme of the purifier



Scheme of the Recovery System






Lay out of the test stand

Status of work - Preparation of Test station

Field Measurement System

Harmonic coil parameters

r1/mm	r2/mm	r3/mm	r4/mm	Mout/turns	Min/turns	Rref/mm
35	23	-25	-17	80	120	35






- ✓ Mainly by the rotating coil.
- ✓ Subsidiarily by Hall probe and NMR probe.
- ✓ The field measurement system is ready.

- Two radius coils symmetric to the axis;
- Outer Coil :main winding
- Inner Coil :dipole bucking which cancel the dipole component: $V_A - V_B$
- Typical accuracy of the system : 10^{-4} .
- The rotating coil is positioned in two anti-cryostats.

Status of work - Preparation of Test station

Quench Detection System



- The two asymmetry voltage bridges are used as the judgement signals to avoid possible symmetry quench.
- Quench detection system is based on the NI-cRIO platform.
- The logical calculus is carried out by FPGA.
- The isolation module is used to protect the electronic equipment.
- When the quench is detected, a 24V quench signal will be sent to trigger the quench protection switch and the data acquisition system.

Steering Committee meetings: Main outcome

The 1st steering committee meeting held in Oct. 7 2019.

Schedule of series magnets The successful test of the prototype is necessary before giving the green light to start the production of the series; for this reason, the beginning of the manufacturing for the series should be shifted by 6 months.

Wires insulation planning The bare wire will be insulated by CGP company (FR). IHEP will agree with them a detailed schedule of deliveries in order to fit with the current planning and communicate the result to CERN.


Prototype delivery The delivery of the prototype to CERN might be shifted to Feb. 2020.

The ST COM takes notes of the delay, not critical for HL-LHC project, and commends the IHEP and all Chinese teams for the increased effort on the prototype and for launching the definition and procurement of important components.

The QA/QC plan has recently been improved in a considerable way, with mutual satisfaction.

Schedule

- Production rate assumption: 1 magnet each 2 months
- Series starts after test on prototype



Schedule

Prototype delivered at CERN (MCBRDP2)	February 2020
1st series magnet test delivered at CERN (MCBRD01)	September 2020
2nd series magnet test delivered at CERN (MCBRD02)	November 2020
1st batch delivered at CERN (MCBRD03-05)	May 2021
2nd batch delivered at CERN (MCBRD06-08)	November 2021
3rd batch delivered at CERN (MCBRD09-12)	July 2022

Manpower

	2019	2020	2021	2022
Scientific (FTE)	8	8	8	8
Technicians (FTE)	8	8	8	8
Total (FTE)	16	16	16	16

Structure



HL LHC WP3: MCBRD

Q. Xu,
S. Wei (deputy)



July 2019

Design
S. Wei, Y. Liang (deputy)

Contract follow-up
J. Wang, D. Ni (deputy)


QA
L. Gong, S. Wei (deputy)

Production
C. Li

Construction
M. Li, Z. Ge (deputy)

Contract
C. Li

QA
Y. Wang, M. Li (deputy)




Test
W. Wu

Room temperature test
Q. Peng, L. Gong (deputy)

4.5 K test
W. Yang, D. Ni (deputy)

QA
Y. Liang, W. Yang (deputy)



Risks, impact, mitigation measures

- **Technical risks**

 - Electrical insulation (quality control)

 - Field quality (Further minor optimization to reduce the field error?)

- **Resource risks**

 - Stable supply of Helium for the cold test

- **Schedule**

 - No serious potential obstacles foreseen presently



Thanks for your attention

